



## MAERA

**Apexindo first submersible swamp barge, built in 1992, added cantilever in 2003 and last dry dock in 2018.  
10,000 Psi BOP System –7,500 Psi WP Mud Pump – 3,000 HP Drawwork**

Design	:	APEXINDO / Protomac 7 to 25 ft water depth; 25,000 ft drilling
Gross Tonnage / LOA	:	3,735 Ton / 68.89 m
Power	:	4 x Caterpillar D-3516 - 1,580 HP each
SCR	:	Ross Hill
Mast	:	Pyramid 1,650,000 lbs GNC
Drawworks	:	Gardner Denver 3,000 HP
Mud Pumps	:	3 x Gardner Denver PZL 1,600 HP 7,500 Psi WP
Rotary table	:	Gardner Denver RT 375. 37½" opening. 550 ton.
Top Drive	:	Varco TDS-4S high torque
Solid Control	:	4 x VSM 300 Shale Shakers - Brandt 1 x SRS-3 desander 1 x SE-16 desilter 1 x VG-I degasser 2 x FVSD HS 3400 centrifuges - Brandt
Mud Pits	:	400 m3 liquid
Bulk Storage	:	3,000 cuft cement; 3,000 cuft barite / bentonite
BOP Equipment	:	29 1/2" x 500 Psi Diverter – Hydril 13 5/8" x 5,000 Psi Annular - Cameron 13 5/8" x 10,000 Psi 4 rams – Cameron
Cantilever	:	Lateral 2 x 12 ft; longitudinal 22 ft
Cranes	:	2 x BMC 900 100 ft boom max hoist 49,965 lbs @20 ft
Living Quarters	:	100 persons; 2 beds in clinic

### PT Apexindo Pratama Duta Tbk

Head Office : Office 8 20th – 21st Floor, SCBD Lot 28 JL. Jend. Sudirman Kav. 52-53 , Jakarta 12190  
Tel. (62-21)29333000 , 29333020 (Hunting) Fax. (62-21) 29333111  
Email: [info@apexindo.com](mailto:info@apexindo.com)

Branch Office : Jl. Jend. Sudirman, Balikpapan Permai Complex, Blok L No. 10-12, Balikpapan 76114  
Tel. (62-542) 410 258 (Hunting) Fax. (62-542) 411 788

Contact Person : Donald Kent Wood (Director/ Independent Director)

**[www.apexindo.com](http://www.apexindo.com)**